

City of Lynchburg, Procurement Division
900 Church Street, Lynchburg, VA 24504
Telephone No: 434-455-3841
Fax No: 434-845-0711

Date: June 11, 2013

From: Deborah J. Powell, CPPB, VCO

RE: Addendum #02 – Re-Bid Sheffield Elementary School Re-roofing Project

In reference to Bid #13-833R issued June 6, 2013, for the above referenced project please amend the proposal as follows as noted below and beginning with page 2 of this document.

This addendum must be signed and returned with the original package.

Deborah J. Powell, CPPB, VCO
Buyer

READ TERMS AND CONDITIONS AND SIGN

In compliance with the above Invitation for Bid, and subject to all the conditions hereof, the undersigned offers and agrees to comply with any or all of the terms and conditions contained herein, or as mutually agreed upon by subsequent negotiations. This form shall become part of the final file.

Company Name: _____

Address: _____

Date: _____

Authorized Signature: _____

Title: _____

Print Name: _____

Telephone #: _____

Fax #: _____

ADDENDUM #2

Name of Project: Sheffield Elementary School Reroofing
Location: Lynchburg, Virginia
Project No. 3207
Date: June 11, 2013

The following items represent changes, modifications and/or clarifications to the Contract Documents for this project. This Addendum shall become a part of the Contract Documents, and all Bidders shall acknowledge its inclusion in their bid.

This Addendum consists of the following:

1 typed page

CHANGES TO SPECIFICATIONS:

Section 07531 – Ethylene-Propylene-Diene-Monomer (EPDM) Roofing:

1. Page 6, Paragraph 2.3 C. Please REVISE this paragraph to read as follows:

- C. Tapered Insulation: Provide factory-tapered insulation boards fabricated to slopes of 1/8 inch per 12 inches (1:96) or 1/4 inch per 12 inches (1:48) [refer to drawings for locations], except at crickets which will be 1/4 inch per 12 inches (1:48) where field slopes at 1/8 inch per 12 inches, and 1/2 inch per 12 inches (1:24) where field slopes at 1/4 inch per foot. Thickness to be minimum 1 1/2" at roof drains.

CHANGES TO DRAWINGS:

Sheets A1.1R and A1.2R, Partial Enlarged New Work Roof Plan:

1. Please refer to Sheets A1.1R and A1.2R issued as part of Addendum #1. Please REVISE the bubbled note on these sheets to read as follows:

TYPICAL SLOPE 1/4" PER FOOT FOR FIELD. CRICKETS IN THIS AREA TO SLOPE AT 1/2" PER FOOT.

END OF ADDENDUM #2