

City of Lynchburg
Procurement Division
900 Church Street
Lynchburg, Virginia 24504
Telephone No.: (434) 455-3970
Fax No.: (434) 845-0711

**Addendum for Invitation for Bids
LCS Department of Transportation Bus Lot Upgrades**

15-945

Date: 01/06/2015
From: Lisa Moss, Buyer VCA
RE: Addendum No. 1

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

1. On sheet E1 Note 3 – states to treat all wood surfaces with one time wood finish. Does this note apply to the 4” x 4” existing posts that are to remain?
Yes.
2. Sheet E1 – reference made to use an Extren series 525 panel to mount the new equipment to. Can you supply required thickness of the FRP panel?
½” thick.
3. 4x4 posts with receptacles to be turned?
Receptacle outlet boxes and cable hangers shall be removed. New receptacle outlet boxes shall be installed facing the busses. Cable hangers shall be reinstalled 90⁰ from current position.
4. Bubble covers to be cast metal?
Weatherproof, while-in-use covers on receptacle outlet boxes shall be cast metal as specified.
5. Are we reusing the existing connections from the power company?
Power company secondary conductors will be reused unless the power company chooses to replace them.
6. Can the space heater be after market?
The space heaters in the panelboard enclosures can be aftermarket. Shop drawing should be provided.
8. Are the cable hangers to be removed and replaced? If so, with what type of material?
New cable hangers may be provided. Shop drawing should be provided.
9. Where are the asphalt spoils to be dumped?
All excavated spoils should be dumped on the existing dirt pile identified during the pre-bid meeting.

Company Name: _____ Address: _____ Date: _____

Authorized Signature: _____ Title: _____

Print Name: _____ Telephone No.: _____

Fax No.: _____