

City of Lynchburg  
Procurement Division  
900 Church Street  
Lynchburg, Virginia 24504  
Telephone No.: (434) 455-3970  
Fax No.: (434) 845-0711

**Addendum for Invitation for Bids  
Abert Water Treatment Plant Electrical Renovations**

**15-937**

Date: 10/10/2014  
From: Lisa Moss, Buyer VCA  
RE: Addendum No. 1

---

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

1. **Site Visits are encouraged and are by appointment only. Appointments can be made by contacting Richard Eden at 434-455-4264.**
2. **The Statement of Qualifications included in the Documentation Form dated September 5, 2014, which is included in the Project Manual pages PM-9 through PM-13, shall be incorporated into the Project Manual and shall be submitted with the bid form. Failure to document the information requested as part of the Statement of Qualifications may be a basis for rejection of the bid as nonconforming.**
3. **The Contractor will be provided access to the existing freight elevator at the Abert WTP. The maximum weight load shall be restricted to 2,000 lbs and freight only. Utilization of the elevator is at the Contractor's sole discretion, and the City makes no guarantee or warranty that it will be operational during the project. Due to the age of the machinery, it is subject to frequent outages of 48 hours or longer. Freight elevator outages shall not be a cause for an adjustment to the Contract Price or Times.**
4. **Normal Working Hours are defined as 7:00 am to 5:00 pm Monday through Friday. If the Contractor intends to work outside Normal Working Hours, it must be scheduled and approved in advance by the City's Project Manager.**
5. **Revise Panel Schedule for Panel LP-2A (Drawing E-604) and Panel LP-2B (Drawing E-605) to indicate "Mount: Surface". The design intent is to surface mount Panels LP-2A and LP-2B and associated junction boxes as shown on Detail C Drawing E-402.**
6. **Contractor is responsible for providing on-site storage for all materials. No materials may be stored in the Abert WTP building. Limited paved and unpaved areas are available on-site.**
7. **Contractor shall obtain and pay for a Building Permit from Bedford County.**
8. **Contractor shall repair and restore any damaged pavement and shall restore and permanently seed and stabilize disturbed grassed areas that were damaged or disturbed by the Contractor in accordance with the City of Lynchburg Manual of Specifications and Standard Details, Latest Edition and the Virginia E&S Regulations.**

**Questions from Bidders:**

9. *Is the city going to take possession of the existing re-located generator after the construction is complete? Or is it the contractor's responsibility to dispose of it.*

The contractor shall dispose of the existing generator after construction is complete.

10. On drawing E-003 note #16 "Says Provide 1-1/2" conduit out of the ATS to Room 207 for remote control station" Please provide the location for this conduit.

Note "16" on sheet E-003 is referring to a conduit from the Generator to room 207 not the ATS. Conduit should turn down the wall adjacent to the "Valve Control Cabinet" for connection to the "Remote Control Station".

11. On drawing E-003 note #16 "Says Provide 1-1/2" conduit out of the ATS to Room 207 for remote control station. Is the control station a "Generator control panel" ?

Yes, it is the generator remote control station and the intent of the design is that it will be supplied with the generator package.

Company Name: \_\_\_\_\_ Address: \_\_\_\_\_ Date: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_ Title: \_\_\_\_\_

Print Name: \_\_\_\_\_ Telephone No.: \_\_\_\_\_

Fax No.: \_\_\_\_\_