

City of Lynchburg  
Procurement Division  
900 Church Street  
Lynchburg, Virginia 24504  
Telephone No.: (434) 455-3970  
Fax No.: (434) 845-0711

**Addendum for Invitation for Bids  
Former Allen Morrison Site- South Side- Soil Remediation  
2016-026**

Date: 10/02/2015  
From: Lisa Moss, Buyer VCA  
RE: Addendum No. 1

---

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

1. We are looking at bidding on the above referenced project. I was curious if the "clean backfill" referred to in the bid documents can be gravel.  
**The required clean backfill shall be certified clean compacted soil backfill, meaning having no contamination, no organic matter, and no foreign objects including stones larger than 3 inches in diameter.**
2. What analytical are you requiring for the soils?  
**The fill material shall be analyzed for RCRA metals, PCBs, TPH-DRO, TPH-GRO, BTEX and PAHs. The analytical results shall be provided for review and approval prior to mobilization.**
3. Does the City require air monitoring during excavation?  
**Yes – see answer to Question 5.**
4. In reference to the lead, are the levels hazardous or non hazardous  
**The soil waste stream has been deemed non-hazardous based on the waste stream analysis included in the Excavation Scope of Work.**
5. Who is responsible for dust monitoring?  
**The contractor shall perform dust monitoring to ensure that the work is performed in accordance with OSHA regulations as discussed in Section 2.4 of the Excavation Scope of Work.**
6. Will there be any additional fencing needed? Who will have access to the site? Will there be areas that are to be kept open and accessible?  
**No additional fencing will be required. The contractor and his employees will have access to the site. The selected employees of the City's Public Works and Parks and Recreation departments will also have access to the site. The Contractor will be given a key to the gate nearest the work area, which he will be required to return to the City upon completion of the project. The Contractor will need to keep access open to the materials stored beside and to the rear of the project work area.**

Company Name: \_\_\_\_\_ Address: \_\_\_\_\_ Date: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_ Title: \_\_\_\_\_

Print Name: \_\_\_\_\_ Telephone No.: \_\_\_\_\_ Fax No.: \_\_\_\_\_