

City of Lynchburg
Procurement Division
900 Church Street
Lynchburg, Virginia 24504
Telephone No.: (434) 455-3970
Fax No.: (434) 845-0711

**Addendum for Invitation for Bids
COL Generator Upgrades**

14-890

Date: 1/28/2014
From: Lisa Moss, Buyer VCA
RE: Addendum No. 1

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

1. REVISION TO CONTRACT DOCUMENTS (PM 11):

ORIGINAL: SHALL SUBSTANTIALLY COMPLETE THE PROJECT WITHIN 90 CALENDAR DAYS.

REVISION: SHALL SUBSTANTIALLY COMPLETE THE PROJECT WITHIN 90 DAYS FROM DATE GENERATOR SHOP DRAWINGS HAVE BEEN APPROVED.

2. Can EMT be used for indoor and outdoor exposure applications?

EMT can be used for INDOOR EXPOSURE applications ONLY.

3. Will the owner consider propane or natural gas generators?

No

4. Does the internet appliance need a source of 120VAC power?

Yes. Pick up 120VAC from nearest receptacle circuit.. Extend circuit and provide duplex receptacle adjacent to appliance.

5. Will there be an internet appliance for each generator?

Yes

6. Can you please advise where you can purchase the internet appliances?

No, that will be the contractors responsibility.

7. Will the generators be full or empty during this project?

The existing tanks may be empty, full or somewhere in between. It is the contractors responsibility to remove whatever fuel is left in them. It is the contractors responsibility to leave the new tanks full at the end of testing/commissioning.

8. Will there be new transfer switches for each generator?

Yes

9. If the existing wires above panel "LV", in Fire Station #1, are too short, can they be spliced within the tophat?

Yes, using clear-taps or terminal blocks. Wire nuts, butt splices, or split bolts will not be allowed.

10. **FIRE STATION #7: BE SURE NOT TO BLOCK ANY APPARTUS OR OTHER OVERHEAD DOORS WITH CONSTRUCTION VEHICLES, MATERIALS, ETC. ALL DOORS ON BOTH SIDES OF BOTH BUILDINGS ARE ACTIVELY USED.**
11. **CHANGE TO PUBLIC WORKS ADMINISTRATION BUILDING DEMOLITION NOTE 1: "REMOVE AND DISPOSE OF EXISTING 15KW GENERATOR AND SUB-BASE FUEL TANK"**
12. **This project will be awarded on Total Base Bid. There is no guarantee of award of the Additive Bid item and the Additive Bid Item will not be considered as part of the base bid.**

Company Name: _____ *Address:* _____ *Date:* _____

Authorized Signature: _____ *Title:* _____

Print Name: _____ *Telephone No.:* _____

Fax No.: _____