

City of Lynchburg  
Procurement Division  
900 Church Street  
Lynchburg, Virginia 24504  
Telephone No.: (434) 455-3970  
Fax No.: (434) 845-0711

**Addendum No. 1 for Invitation for Bids  
Jefferson Park  
2016-073**

Date: 06/23/16  
From: Lisa Moss, Buyer VCA  
RE: Addendum No. 1

---

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

- 1. Dual wall, watertight HDPE pipe is recommended for this application.**
- 2. Refer to attached Figure 1 – Geoprobe Locations for information regarding depth to waste from existing grade along the proposed swales.**
- 3. The Bidder can use the attached Figure 1 and site observations to estimate the volume of waste that may be generated for disposal at a landfill. If waste is encountered, it shall be over excavated by 2'-0" and refilled with compacted soil. Waste must be collected in container at time of removal and covered for final transport to the Region 2000 landfill in Rustburg VA.**
- 4. Can the amount of 120 calendar days to complete the work be extended? *This project must be completed no later than November 30, 2016. Once construction is underway, if conditions on the site warrant expanding the work schedule into weekends/holidays, we would consider that as an option at that time.***
- 5. Will there be a fee associated with trash that needs to go the Landfill and is the contractor responsible for that fee? *The Contractor is responsible for all disposal fees.***
- 6. Is the contractor or City responsible for any testing? *No, the City will be responsible for testing at the site***
- 7. Being that the work will be in close proximity to the Jefferson Park Apartments will there be any changes to the time we are allowed to work? *The City of Lynchburg Noise Ordinance will apply in this instance. The ordinance prohibits work between 9 PM to 7 AM daily.***
- 8. Page 10 of the SWPPP plan says new vegetation will need to be maintained for 1 year after planting. Is this something the Contractor will need to do and if so what specifically does that include having to do? *No, the City will assume maintenance responsibility of plantings upon completion of the project.***
- 9. The detail for sidewalk shows stone under the concrete extending out further than the concrete, is this extra stone needed? If so the detail does not tell us how far outside of the concrete the stone goes. *The stone does not need to extend further out than the concrete.***

**10.** Can we get some clarification on some details? For the storm trench there is one detail and then there is another detail for the North Storm Bedding and they each show different things. They each call for different stone for bedding. One shows Clay lining the trench the other doesn't. Is clay needed to line all of the storm trenches or just where there is a gas vent since it only shown on that detail? *The north storm sewer bedding and backfill detail should be used for the storm line from structures 20-28. The City of Lynchburg standard storm bedding detail should be used for the pipe downstream of structure 32.*

Company Name: \_\_\_\_\_ Address: \_\_\_\_\_ Date: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_ Title: \_\_\_\_\_

Print Name: \_\_\_\_\_ Telephone No.: \_\_\_\_\_ Fax No.: \_\_\_\_\_