

City of Lynchburg
Procurement Division
900 Church Street
Lynchburg, Virginia 24504
Telephone No.: (434) 455-3970
Fax No.: (434) 845-0711

**Addendum for Invitation for Bids
REISSUED
Wards Road Pedestrian/Bike Trail Phase IIB**

14-862

Date: 12/11/2013
From: Lisa Moss, Buyer VCA
RE: Addendum No. 2

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

- 1. A SECOND REVISION HAS BEEN MADE TO THE BID SHEET. A REVISED BID SHEET IS ATTACHED BELOW.**
- 2. THE BID SUBMISSION DATE AND TIME HAS BEEN CHANGED TO DECEMBER 19, 2013 AT 4:00 P.M.**

Company Name: _____ *Address:* _____ *Date:* _____

Authorized Signature: _____ *Title:* _____

Print Name: _____ *Telephone No.:* _____

Fax No.: _____

Wards Road Pedestrian/Bicycle Trail - Phase IIB

DATE: _____

CITY PROJECT NO.:

W/JV PROJECT NO.: 211077.00

Bid Schedule: Revised 12-11-2013

DEMOLITION					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
DM-1	SAWCUT AND REMOVE EXISTING CURB & GUTTER	L.F.	55.00		
DM-2	TREE REMOVAL	EA.	10.00		
				SUBTOTAL	

PAVEMENT, CURB & GUTTER & SIDEWALKS					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
PA-1	PAVEMENT PROFILING - 1-1/2 INCHES FOR STREETPRINT XD CROSSWALKS	S.Y.	40.00		
PA-2	PAVEMENT OVERLAY - 1-1/2 INCHES SM-9.5A	S.Y.	80.00		
PA-3	6-INCH CONCRETE CURBING (INCLUDING AGGREGATE BASE)	L.F.	250.00		
PA-4	CG-6 CURB & GUTTER (INCLUDING AGGREGATE BASE)	L.F.	80.00		
PA-5	NEW CONCRETE SIDEWALK, 5" THICK	S.Y.	750.00		
PA-6	TYPE I, SIZE 21 OR 21A AGGR. BASE (4" LAYER) - FOR SIDEWALKS	S.Y.	750.00		
PA-7	NEW CONCRETE HANDICAP RAMP (CUSTOM)	EA.	4.00		
PA-8	CROSSWALK - STREETPRINT XD	S.F.	385.00		
PA-9	CROSSWALK - THERMOPLASTIC STRIPING	S.F.	150.00		
				SUBTOTAL	

OTHER ITEMS					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
MS-1	SELECT BORROW	C.Y.	100.00		
MS-1a	UNDERCUT AND BACKFILL (UNSUITABLE MATERIAL)	C.Y.	50.00		
MS-2	TEMPORARY SEEDING	S.Y.	1,200.00		
MS-3	PERMANENT SEEDING	S.Y.	1,200.00		
MS-4	SILT FENCE BARRIER	L.F.	350.00		
MS-5	FINE GRADING (5' AROUND NEW SIDEWALK)	S.Y.	1,000.00		
MS-6	2" CONDUIT AND PULL STRING FOR STREET LIGHTS	L.F.	1,750.00		
MS-7	TRAIL LIGHT CONC. BASE (2" DIAMETER)	EA.	26.00		
MS-8	FORMED CONCRETE STEPS (VDOT STD. S-2)	C.Y.	10.00		
MS-9	HANDRAIL (VDOT STD. HR-1)	L.F.	105.00		
MS-10	GUARDRAIL (MODIFICATION / RELOCATION)(INCLUDING END TREATMENTS AS INDICATED)	L.F.	900.00		
MS-11	ELEVATED WALKWAY (W/ SINGLE HANDRAIL)	L.F.	413.00		
MS-12	ELEVATED WALKWAY (W/ DOUBLE HANDRAIL)	L.F.	56.00		
MS-13	CROSSWALK SIGNAGE (INCLUDING "STOP" SIGNS)	EA.	10.00		
MS-14	TRAIL SIGNAGE (1.5'x2')	EA.	3.00		
MS-15	15" CLASS III, REINFORCED CONCRETE PIPE	L.F.	20.00		
MS-16	DRY RIPRAP CLASS AI UNGROUTED	TONS	2.00		
MS-17	SURVEY STAKEOUT	L.S.	1.00		
MS-18	TRAFFIC CONTROL	L.S.	1.00		
MS-19	MOBILIZATION (5%)	L.S.	1.00		
				SUBTOTAL	

Note: 1. Contractor shall verify quantities to his own satisfaction prior to placing bid.

PROJECT TOTAL	
---------------	--

BID ALTERNATE #A			
ITEM NO.	DESCRIPTION	UNIT	ADDITION / SUBTRACTION (CIRCLE ONE)
ALT. #A	SUBSTITUTE METAL GRATING FOR COMPOSITE DECKING ON ELEVATED WALKWAYS (SEE DETAIL SHEET C-302)	LS	

BID ALTERNATE #B					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
ALT. #B	EMERGENCY CALL BOX (CODE BLUE "CB 9-S" W/ FP-1 FACEPLATE) (SEE SHEET C-102)	EA	1.00		

BID ALTERNATE #C					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
AC-1	NEW CONCRETE SIDEWALK, 5" THICK	S.Y.	165.00		
AC-2	TYPE I, SIZE 21 OR 21A AGGR. BASE (4" LAYER) - FOR SIDEWALKS	S.Y.	165.00		
AC-3	CONCRETE PIERS FOR LIGHT POSTS	EA.	4.00		
AC-4	ELEVATED WALKWAY (W/ SINGLE HANDRAIL) (SUBTRACT)	L.F.	-240.00		
AC-5	TRAIL LIGHT CONC. BASE (2" DIAMETER) (SUBTRACT)	EA	-4.00		
AC-6	RETAINING WALL (W/ SINGLE HANDRAIL)	L.F.	250.00		
AC-7	TREE REMOVAL	EA	4.00		
				SUBTOTAL	