

City of Lynchburg
Procurement Division
900 Church Street
Lynchburg, Virginia 24504
Telephone No.: (434) 455-3970
Fax No.: (434) 845-0711

**Addendum for Invitation for Bids
Wards Road Pedestrian/Bike Trail Phase IIB**

14-862

Date: 08/23/2013
From: Lisa Moss, Buyer VCA
RE: Addendum No. 1

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents. The Bidder shall indicate receipt of this Addendum and all previously issued Addenda on the Bid Form.

1. Please clarify the terms of a temporary shutdown of the project during the holiday season. Please also advise who will make the decision to shut down.
 - (A) **Work along Wards Road and adjacent to existing businesses, including parking areas, that requires lane closures or will impact the existing parking areas will not be allowed between November 28, 2013 and December 31, 2013. Work along Harvard Street as well as work that does not impact current traffic pattern or business parking will be allowed during this time.**

2. **Bid sheet has been revised as listed below. Revised Bid sheet is attached.**
 - Removing line item MS13 for Blue Emergency Call Box. This will remain as an alternate on this project.**

 - Line item MS-1a has been added to include "Undercut and backfill for Unsuitable Materials".**

3. **This project includes work to be performed within easements. All easements for this project have been obtained.**

4. **Traffic control procedures must be in-line with VA Work Area Protection guidelines.**

5. Please clarify footing depth shown on Drawing C302.
 - (A) **The bottom of all footings must be at least 2'-0" below finished grade. Total height of the footings will vary. Sheet C-302 has been updated.**

6. Are there any Federal Funds involved in this project? Ex..Davis Bacon, DBE requirements?
No Federal Funds are being used for this project.

7. Please clarify when the 120 calendar days for this project will actually start.
 - (A) **The length of the project will be extended to 165 calendar days. This time frame will begin on the date listed on the contractors "Notice to Proceed". This City anticipates this date to be around the first of October.**

8. **Project award will be as stated on PM-24 Section 9 Award of Contract.**

9. **Contact information for Ohio Grating:**
Ohio Grating

10. Is the metal on S3 Sheet C302 to be galvanized?
(A) **All structural steel shall be primed and painted per note 3 on C-302 and the primer/paint notes listed in response to question 13 below. If the bid alternate is selected the grating will be galvanized.**
11. Can you provide the specifications for the Top and Bottom railing and Pickets?
(A) **Material specifications are listed in Structural Steel notes.**
12. Are shop drawings to be submitted prior to start of project?
(A) **Yes. Shop drawings are required for all structural steel framing and railings.**
13. Please clarify the paint specifications on this project?
(A) **Black paint shall match the Wards Road pedestrian bridge:
SSPC-SP6
S-W Corothane 1 GalvaPac 1K
Zinc Primer (B65G11)
S-W Fastclad Urethane (B65-950)
Apply per manufacturer recommendations.**
14. All testing for this project shall be as specified by the “City Engineer” and shall be in accordance with the City of Lynchburg Manual of Specifications 2012. Anticipated testing requirements will include concrete testing. Section 3.1.5 of the City’s Manual of specifications references VDOT Road and Bridge Specification section 217.08-Acceptance, which includes Air and Strength Testing requirements. Cost for testing shall be included within the associated line items.
15. Who will be responsible for the compaction testing?
(A) **Materials testing shall be performed in accordance with the City Lynchburg Manual of Specification, latest edition. Testing requirement shall be as specified by the “City Engineer”. Cost for testing shall be included within the associated line items.**
16. E & S approvals: What guidelines should they follow?
(A) **Anticipated E&S measures are shown on the plans and have been approved by the City’s E&S Administrator. Refer to General Notes shown on sheet G-001 for additional E&S and land disturbance permit requirements.**
17. **In addition to the above questions, detail “S7” on sheet C-302 has been modified.**

Company Name: _____ Address: _____ Date: _____

Authorized Signature: _____ Title: _____

Print Name: _____ Telephone No.: _____

Fax No.: _____

Wards Road Pedestrian/Bicycle Trail - Phase IIB

DATE: _____

CITY PROJECT NO.:

WJW PROJECT NO.: 211077.00

Bid Schedule: Revised 8-20-2013

DEMOLITION					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
DM-1	SAWCUT AND REMOVE EXISTING CURB & GUTTER	L.F.	55.00		
DM-2	TREE REMOVAL	EA.	10.00		
			SUBTOTAL		

PAVEMENT, CURB & GUTTER & SIDEWALKS					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
PA-1	PAVEMENT PROFILING - 1-1/2 INCHES FOR STREETPRINT XD CROSSWALKS	S.Y.	40.00		
PA-2	PAVEMENT OVERLAY - 1-1/2 INCHES SM-9.5A	S.Y.	80.00		
PA-3	6-INCH CONCRETE CURBING (INCLUDING AGGREGATE BASE)	L.F.	250.00		
PA-4	NEW CONCRETE SIDEWALK, 5" THICK	S.Y.	875.00		
PA-5	TYPE I, SIZE 21 OR 21A AGGR. BASE (4" LAYER) - FOR SIDEWALKS	S.Y.	875.00		
PA-6	NEW CONCRETE HANDICAP RAMP (CUSTOM)	EA.	4.00		
PA-7	CROSSWALK - STREETPRINT XD	S.F.	385.00		
PA-8	CROSSWALK - THERMOPLASTIC STRIPING	S.F.	150.00		
			SUBTOTAL		

OTHER ITEMS					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
MS-1	SELECT BORROW	C.Y.	100.00		
MS-1a	UNDERCUT AND BACKFILL (UNSUITABLE MATERIAL)	C.Y.	50.00		
MS-2	TEMPORARY SEEDING	S.Y.	1,200.00		
MS-3	PERMANENT SEEDING	S.Y.	1,200.00		
MS-4	SILT FENCE BARRIER	L.F.	350.00		
MS-5	FINE GRADING (5' AROUND NEW SIDEWALK)	S.Y.	1,000.00		
MS-6	2" CONDUIT AND PULL STRING FOR STREET LIGHTS	L.F.	1,750.00		
MS-7	TRAIL LIGHT CONC. BASE (2' DIAMETER)	EA.	26.00		
MS-8	FORMED CONCRETE STEPS (VDOT STD. S-2)	C.Y.	10.00		
MS-9	HANDRAIL (VDOT STD. HR-1)	L.F.	105.00		
MS-10	GUARDRAIL (MODIFICATION / RELOCATION)(INCLUDING END TREATMENTS AS INDICATED)	L.F.	900.00		
MS-11	ELEVATED WALKWAY (W/ SINGLE HANDRAIL)	L.F.	413.00		
MS-12	ELEVATED WALKWAY (W/ DOUBLE HANDRAIL)	L.F.	56.00		
MS-13	CROSSWALK SIGNAGE (INCLUDING "STOP" SIGNS)	EA.	10.00		
MS-14	TRAIL SIGNAGE (1.5'x2')	EA.	3.00		
MS-15	15" CLASS III, REINFORCED CONCRETE PIPE	L.F.	20.00		
MS-16	CONCRETE SIDEWALK TRENCH TO OUTFALL W/ METAL GRATING	EA.	1.00		
MS-17	DRY RIPRAP CLASS AI UNGROUTED	TONS	25.00		
MS-18	SURVEY STAKEOUT	L.S.	1.00		
MS-19	TRAFFIC CONTROL	L.S.	1.00		
MS-20	MOBILIZATION (5%)	L.S.	1.00		
			SUBTOTAL		

Note: 1. Contractor shall verify quantities to his own satisfaction prior to placing bid.

PROJECT TOTAL	
---------------	--

BID ALTERNATE #A			
ITEM NO.	DESCRIPTION	UNIT	ADDITION / SUBTRACTION (CIRCLE ONE)
ALT. #A	SUBSTITUTE METAL GRATING FOR COMPOSITE DECKING ON ELEVATED WALKWAYS (SEE DETAIL SHEET C-302)	LS	

BID ALTERNATE #B					
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	Unit Price	Amount
ALT. #B	EMERGENCY CALL BOX (CODE BLUE "CB 9-S" W/ FP-1 FACEPLATE) (SEE SHEET C-102)	EA	1.00		