

City of Lynchburg
Procurement Division
900 Church Street
Lynchburg, VA 24504
Phone: (434) 455-3970
Fax: (434) 845-0711

Addendum for Bid
Langhorne Road Bridge Renovation and Blackwater Creek
Trail Extension to Linkhorne Middle School

2020-013

Date: 9/9/2019

From: Melissa Tillman, Contract Specialist

RE: Addendum No. 2

This Addendum becomes a part of the bidding documents and modifies the Project Manual and Drawing as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject bidder to disqualification.

1. **Question:** I have had a couple of our subcontractors ask about the seeding. There is only an item for seeding. What about the fertilizer and lime?
Response: The bid sheet has been revised to include line items for temporary seed, fertilizer and lime, see **Attachment A.**

2. **Question:** Also, Sheet 8 (8) of the plan set details the Static Sign and Banner System. We are unclear on what a “Static Sign” is. Could you provide a supplier of the requested material?
Response: The static sign consists of single metal letters, typical to those used on buildings for companies, that are attached and don’t intend to move.

3. **Question:** Sheet 8(11) of the plan set outlines the requirements for the Gabion Walls. The last note on the sheet indicates the wall system proposed may be substituted with some other system. There is no mention of any aesthetic requirements, am I to assume any substitution is acceptable as long as it meets the design requirements. We are looking into the possibility of using a masonry landscape block in lieu of the gabion wall design. Personally, I think it will be much more aesthetically pleasing than the gabion walls proposed. Please advise.
Response: All wall alternatives are acceptable that meet the design requirements.

READ TERMS AND CONDITIONS AND SIGN

In compliance with the above BID, and subject to all the conditions hereof, the undersigned offers and agrees to comply with any or all of the terms and conditions contained herein, or as mutually agreed upon by subsequent negotiations. This form shall become part of the final file.

Company Name: _____ *Address:* _____ *Date:* _____

Authorized Signature: _____ *Title:* _____

Print Name: _____ *Telephone No.:* _____ *E-mail:* _____

Attachment: A- Revised Bid Sheet

REVISED BID SHEET

(Updated 9.9.2019)

Item No.	VDOT Bid Item No.	Item Description	Quantity	Unit	Cost	Total
1	100	MOBILIZATION	1	LS		
2	101	CONSTRUCTION SURVEYING	1	LS		
3	111	CLEARING AND GRUBBING	2	ACRE		
4	120	REGULAR EXCAVATION (See Note 1 below)	6,182	CY		
5	140	BORROW EXCAVATION	1,835	CY		
6	290	SELECT MATERIAL TYPE II MIN. CBR-30	100	CY		
7	355	GEOTEXTILE SUBGRADE STABILIZATION	300	SY		
8	1182	18" CONCRETE PIPE	515	LF		
9	6181	18" END SECTION ES-1	1	EA		
10	6770	DROP INLET DI-2C, L=16'	1	EA		
11		MANHOLE MH-1	9	LF		
12		FRAME & COVER MH-1	2	EA		
13	10099	AGGREGATE MATERIAL NO. 21A	1,069	TON		
14	10635	ASPHALT CONCRETE TYPE SM-9.5A	335	TON		
15	11070	NS SAW-CUT ASPHALT CONCRETE	137	LF		
16	12022	RADIAL CURB CG-2	32	LF		
17	13108	CG-12 DETECTABLE WARNING SURFACE	3	SY		
18	13220	HYDRAULIC CEMENT CONCRETE SIDEWALK 4"	29	SY		
19	13244	NS SAW CUT HYDRAULIC CEMENT CONCRETE ITEMS	16	LF		
20	22685	FENCE WOOD BOARD - 4-BOARD FENCE	162	LF		
21	22685	FENCE WOOD BOARD - SPLIT RAIL FENCE	126	LF		
22	22685	FENCE WOOD BOARD - PRIVACY FENCE	476	LF		
23	24501	NS REMOVE EXISTING - PIPE	181	LF		
24	24602	REMOVE EXISTING CHAIN LINK FENCE	190	LF		
25	24810	NS RESET EXISTING - RESET EXISTING PET WASTE STATION	1	EA		
26	27030	NS TOPSOIL - 3" TOPSOIL	30	CY		
27	27030	NS FILL SOIL	50	CY		
28	27012	TOPSOIL CLASS A 2"	1.46	ACRE		
29	27102	REGULAR SEED	308	LB		
30	27104	LEGUME SEED	13	LB		
31	27325	ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	37	SY		
32	27430	SILTATION CONTROL EXCAVATION	492	CY		
33	27461	INLET PROTECTION, TYPE B	1	EA		
34	27505	TEMPORARY SILT FENCE TYPE A	2,862	LF		
35		STABILIZED CONSTRUCTION ENTRANCE EC-11	3	EA		
36	28805	BED PREPARATION	41	UNIT		

REVISED BID SHEET

(Updated 9.9.2019)

37	28810	MULCHING	38	CY		
38	38920	NS BENCH	1	EA		
39	38925	NS TRASH RECEPTACLE	1	EA		
40	39001	NS TREE - RED MAPLE	1	EA		
41	39001	NS TREE - ALLEGHENY SERVICEBERRY	3	EA		
42	39001	NS TREE - EASTERN REDBUD	5	EA		
43	39001	NS TREE - WHITE FRINGETREE	5	EA		
44	39001	NS TREE - CAROLINA SILVERBELL	2	EA		
45	39001	NS TREE - AMERICAN HOLLY	6	EA		
46	39001	NS TREE - EASTERN RED CEDAR	4	EA		
47	39001	NS TREE - VIRGINIA PINE	5	EA		
48	39002	NS SHRUB - BRILLIANTISSIMA CHOKEBERRY	11	EA		
49	39002	NS SHRUB - RED TWIG DOGWOOD	18	EA		
50	39002	NS SHRUB - DWARF FOTHERGILLA	30	EA		
51	39002	NS SHRUB - COMMON WITCH HAZEL	6	EA		
52	39002	NS SHRUB - NIGRA INKBERRY	34	EA		
53	39002	NS SHRUB - RED SPRITE WINTERBERRY HOLLY	34	EA		
54	39002	NS SHRUB - JIM DANDY WINTERBERRY HOLLY (MALE)	7	EA		
55	39002	NS SHRUB - VIRGINIA SWEETSPIRE	58	EA		
56	39002	NS SHRUB - ROSEUM PINK RHODODENDRON	17	EA		
57	39003	NS PERENNIALS - BLUE FALSE INDIGO	39	EA		
58	39003	NS PERENNIALS - THREADLEAF COREOPSIS	47	EA		
59	39003	NS PERENNIALS - PURPLE CONEFLOWER	18	EA		
60	39003	NS PERENNIALS - BLACK EYED SUSAN	19	EA		
61	39004	NS SEED MIXTURE - CONSERVATION SEEDING - SEED MIX "A"	2	LB		
62	39004	NS SEED MIXTURE - CONSERVATION SEEDING - SEED MIX "B"	1	LB		
63	50108	SIGN PANEL	23.25	SF		
64	50300	REMOVE EXISTING 1 POST SIGN STRUCTURE	4	EA		
65	50340	RELOCATE EXISTING 1 POST GROUND MOUNT SIGN PANEL	4	EA		
66	50430	SIGN POST STP-1, 2", 14 GAGE	102	LF		
67	50485	CONCRETE SIGN FOUNDATION STP-1, TYPE A	9	EA		
68	54032	TYPE B CLASS I PAVEMENT LINE MARKING 4"	306	LF		
69	54105	ERADICATION OF EXISTING LINEAR PAVEMENT MARKING	306	LF		
70		PAVEMENT MESSAGE, 2' CHARACTER, TYPE B, CLASS I	96	EA		

REVISED BID SHEET

(Updated 9.9.2019)

71	67088	CHAIN LINK FENCE	350	LF		
72	67088	CHAIN LINK FENCE WITH BARBED WIRE	144	LF		
73	67090	NS PEDESTRIAN FENCE - 9' HIGH ORNAMENTAL BRIDGE FENCING	222	LF		
74	68476	NS ENVIRONMENTAL AND WORKER PROTECTION	1	LS		
75	68492	NS MATERIAL DISPOSAL	1	LS		
76	68900	NS REMOVE PORTION OF EXISTING STRUCTURE	1	LS		
77	68902	TIMBER RAILING	602	LF		
78	68902	STEEL EXPANSION JOINT	48	LF		
79	68902	GABION RETAINING WALL	141	LF		
80	68906	DECKING	3,683	SF		
81	68908	LANGHORNE ROAD PROTECTION SYSTEM	1	LS		
82	68908	STATIC SIGNS AND BANNER SYSTEM	1	LS		
83	68908	STRUCTURAL STEEL MODIFICATION	1	LS		
84	68908	GATE	1	LS		
85	85003	UNDERCUT EXCAVATION AT TWICE REGULAR EXCAVATION	100	CY		
86	85012	NS - HINGED BOLLARD	1	EA		
87	85012	NS - PET WASTE STATION	1	EA		
88	27101	TEMPORARY SEED	435	LB		
89	27215	FERTILIZER (15-30-15)	438	LB		
90	27250	LIME	3	TON		
					TOTAL	