

1. THE PLANS ARE DIAGRAMMATIC AND INDICATE ONLY THE SIZE AND GENERAL ARRANGEMENT OF PIPING AND EQUIPMENT. EXACT LOCATION OF ALL ELEMENTS SHALL BE DETERMINED AS WORK PROGRESSES IN ACCORDANCE WITH THE WORK OF ALL OTHER TRADES.
2. IT IS NOT INTENDED TO SHOW EVERY ITEM OF WORK OR MINOR PHASE OF EQUIPMENT, BUT THE CONTRACTOR SHALL BE RESPONSIBLE FOR IDENTIFYING ANY MISSING ITEMS.
3. IT IS COMPONENT NECESSARY TO COMPLETE THE SYSTEM IN ACCORDANCE WITH THE BEST PRACTICE.
4. ITEMS OF EQUIPMENT SHOWN ON THE DRAWINGS ONLY, OR CALLED FOR IN THE SPECIFICATIONS ONLY, SHALL BE FURNISHED AND INSTALLED IN THE SAME MANNER AS IF THEY WERE SHOWN ON THE DRAWINGS AND SPECIFICATION.
5. DRAWINGS DO NOT INDICATE ALL OFFSETS, CHANGES IN ELEVATIONS, ETC., WHICH MAY BE REQUIRED. THE CONTRACTOR SHALL MAKE SUCH CHANGES IN PIPING AND LOCATION OF EQUIPMENT, ETC. TO ACCOMMODATE WORK WITH THAT OF OTHER CONTRACTORS.
6. INSTALL EQUIPMENT AND PIPING TO AVOID INTERFERENCE WITH THE OPERATION OR SERVISING AND MAINTENANCE OF EQUIPMENT.
7. PIPES PENETRATING FIRE WALLS AND FLOORS SHALL BE FIRESTOPPED AS SPECIFIED, REFER TO THE ARCHITECTURAL DRAWINGS FOR FIRE WALL AND FLOOR LOCATIONS.
8. ALL PHYSICAL ATTRIBUTES OF EQUIPMENT AND DEVICES ARE BASED ON THOSE MANUFACTURERS LISTED IN THE SPECIFICATIONS AND/OR THE EQUIPMENT SCHEDULES. THE REQUIREMENTS BY OTHER MANUFACTURERS FOR ALL CHANGES BROUGHT ABOUT BY USE OF ITEMS BY OTHER MANUFACTURERS. THE ARCHITECT/ENGINEER HAS RESERVED THE RIGHT TO REQUEST ITEMS BY OTHER MANUFACTURERS IF THOSE ITEMS DO NOT MATCH THE PHYSICAL ATTRIBUTES OF THE MANUFACTURERS LISTED.
9. COMPLY WITH THE VIRGINIA STATE BUILDING CODES, VIRGINIA STATE ENERGY CONSERVATION CONSTRUCTION CODE, AND OTHER APPLICABLE CODES.




301 Kemper Street PO Box 797
Lynchburg, VA 24505-0797

PROJECT ADDRESS:


19 Bradley Dr.
Lynchburg, VA
24501-4901

Operations & Maintenance Facility

BID DOCUMENTS



ALEXANDRIA ARCHITECTURE, ENGINEERING,
LAND SURVEYING & LANDSCAPE ARCHITECTS, INC



NOTE:
THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF THE ARCHITECT AND OWNER AND IS NOT TO BE USED IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF THE ARCHITECT AND ENGINEER. UNAUTHORIZED ALTERATION OR ADDITION TO ANY SURVEY, DRAWING, DESIGN, SPECIFICATION, PLAN OR REPORT IS PROHIBITED IN ACCORDANCE WITH STATE LAW, CODE AND RULES.




Revision Number	Issued by	Revision Description	Revision Date
DWG. TITLE			

EQUIPMENT SYMBOLS, NOTES AND ABBREVIATIONS

DATE	09/24/2014		
SCALE	AS NOTED		
DWN.	CCA	CHK.	CRL
PROJ. NO.	444505		

Q001



1 PARTIAL FIRST FLOOR EQUIPMENT PLAN- AREA A
SCALE: 1/8" = 1'-0"



- CONSTRUCTION NOTES:**
1. PROVIDE 4" HIGH EQUIPMENT PAD. EXTEND PAD A MINIMUM OF 6" BEYOND EQUIPMENT FOOTPRINT IN ALL DIRECTIONS. REFER TO STRUCTURAL DRAWINGS FOR FURTHER DETAIL.
 2. TWO POST SCISSOR LIFT AND CONTROLLER TO BE RELOCATED FROM EXISTING FACILITY. CONTRACTOR TO DISCONNECT, RELOCATE, AND INSTALL LIFT WITHIN NEW FACILITY. CONTRACTOR IS RESPONSIBLE FOR ALL COASTS ASSOCIATED WITH RELOCATION OF THE EXISTING LIFT. CONTRACTOR SHALL REPLACE ANY DAMAGED PARTS RESULTING FROM RELOCATION. PROVIDE CONDITION ASSESSMENT REPORT OF EXISTING LIFT AND SUBMIT TO OWNER FOR APPROVAL PRIOR TO REMOVAL. PROVIDE ALL HARDWARE, ELECTRICAL, AND PLUMBING TO ACCOMMODATE LIFT INSTALLATION AND MAKE A COMPLETE AND OPERABLE SYSTEM.
 3. PROVIDE 3" SCHEDULE 40 BLACK STEEL VENT PIPING FROM CABINET UP THROUGH ROOF AND TERMINATE WITH APPROVED NORMALLY OPEN VENT CAP.
 4. PROVIDE EXHAUST EXTRACTION REEL AS SCHEDULED. SUPPORT REEL FROM COLUMN. PROVIDE DELEGATED DESIGN FOR REEL SUPPORT. REFER TO MISCELLANEOUS METALS SPECIFICATIONS FOR FURTHER DETAIL.



PROJECT ADDRESS:
419 Bradley Dr.
Lynchburg, VA
24501-4901

Operations &
Maintenance Facility

BID DOCUMENTS





Revision	Issued By	Revision Description	Revision Date
000		000	

PARTIAL FIRST FLOOR
EQUIPMENT PLAN-
AREA A


DATE	09/24/2014
SCALE	AS NOTED
DRAWN	CCA
CHECKED	CRL
PROJECT NO.	444505
DRAWING NO.	

Q101




① GLASS RACK
SCALE: NOT TO SCALE

NOTE:
ALL WOOD, INCLUDING PLYWOOD, LUMBER AND ALL
OTHER WOOD PRODUCTS, TO BE
FIRE-RETARDANT-TREATED WOOD PER ICC IBC/VUSBC
SECTION 2303.2.



NOTE:
ALL WOOD, INCLUDING PLYWOOD, LUMBER AND ALL
OTHER WOOD PRODUCTS, TO BE
FIRE-RETARDANT-TREATED WOOD PER ICC IBC/VUSBC
SECTION 2303.2.

② BATTERY BENCH
SCALE: NOT TO SCALE



③ VEHICLE EXHAUST HOSE REEL DETAIL
SCALE: NOT TO SCALE



GREATER LYNCHBURG TRANSIT
COMPANY
1301 Kemper Street, PO Box 707
Lynchburg, VA 24505-0797


PROJECT ADDRESS:
419 Bradley Dr.
Lynchburg, VA
24501-4901

Operations &
Maintenance Facility

BID DOCUMENTS



1420 King Street, Suite 510
Alexandria, VA 22314
www.wendelcorp.com
p.703.299.8718 f.703.299.8719
ALEXANDRIA ARCHITECTURE, ENGINEERING,
LAND SURVEYING & LANDSCAPE ARCHITECTS, INC.



KEY PLAN

NOTE:
PORTLAND CEMENT AND THE SOIL ARE TO BE USED IN CONFORMANCE WITH THE
REQUIREMENTS OF THE SPECIFICATIONS FOR PORTLAND CEMENT AND
PORTLAND CEMENT CONCRETE, ASTM C 150 AND C 39, RESPECTIVELY.
WITHOUT THE WRITTEN AUTHORIZATION OF THE ARCHITECT AND ENGINEER,
NO CHANGES OR MODIFICATIONS TO THE DESIGN OR CONSTRUCTION SHALL
BE MADE OR PERMITTED.



Revision Number	Issued By	Revision Description	Revision Date
001	CCA	001	09/24/2014

EQUIPMENT DETAILS

DATE	09/24/2014
SCALE	AS NOTED
DRAWN	CCA
CHECKED	CRL
PROJECT NO.	444005
DRAWING NO.	

Q201

