

NOTES:

24. RPDA'S SHALL BE INSTALLED ABOVE GROUND IN AN ASSE 1060 APPROVED HEATED ENCLOSURE.
25. SHUT OFF VALVES ARE TO BE SHIPPED FROM THE MANUFACTURER AS PART OF THE UNIT. NO SUBSTITUTIONS SHALL BE PERMITTED.
26. THE LINE SHALL BE FLUSHED THOROUGHLY BEFORE INSTALLING THE RPDA TO PREVENT ANY DEBRIS FROM FOULING THE CHECK VALVES CAUSING THE UNIT TO FAIL THE TEST.
27. A STRAINER IS SUGGESTED BUT NOT MANDATORY.
28. NO BYPASS IS ALLOWED AROUND ANY RPDA OR RPZ ASSEMBLY. NO TAKEOFFS OR CROSS CONNECTIONS ARE ALLOWED IN FRONT OF ANY RPDA OR RPZ.



THE CITY OF LYNCHBURG

TURBO METER VALVE WITH
FIRE LINE RPDA COMBINATION

USE WITH THE CITY OF LYNCHBURG STANDARD SPECIFICATIONS ONLY

SCALE:
NOT TO SCALE

DETAIL #
26.20

REVISION DATE:
12-12-2014

SHEET #:
4 OF 4