

LEGEND

- ① ANCHOR BLOCKING – SEE STANDARD DETAIL 26.02.
- ② TIE ROD ANCHORS – SEE STANDARD DETAIL 26.03.
- ③ AWWA C-509 RESILIENT WEDGE GATE VALVE.
- ④ MECHANICAL JOINT RESTRAINT (RESTRAINED JOINT THRUST RINGS) (TYP. OF 10)

NOTES:

1. ALL PIPE AND FITTINGS USED INSIDE THE ENCLOSURE SHALL BE FLANGED DUCTILE IRON. CONCRETE FOR SUPPORTS AND ANCHORS SHALL BE 3000 PSI.
2. ALL NON-FLANGED FITTINGS SHALL BE TIED WITH THREADED ROD TO ADJACENT FITTINGS AS GENERALLY SHOWN ON THIS SHEET. MEGALUG OR APPROVED EQUAL MAY BE SUBSTITUTED FOR TIE RODS AT MECHANICAL JOINTS.
3. ALL DIMENSIONS SHALL BE VERIFIED BY CONTRACTOR.
4. ONE ACCESS DOOR KEY SHALL BE SUBMITTED TO THE METER SUPERVISOR WITH THE DEPARTMENT OF WATER RESOURCES.
5. UPON COMPLETION OF INSTALLATION CONTRACTOR SHALL NOTIFY THE COMPLIANCE SPECIALIST AT 434-455-4261. AN INITIAL TEST SHALL BE PERFORMED BY A STATE CERTIFIED BACKFLOW PREVENTION DEVICE WORKER TO VERIFY THE ASSEMBLY IS FUNCTIONING CORRECTLY WITH A COPY OF A PASSING TEST SUBMITTED TO THE DEPARTMENT OF WATER RESOURCES. AFTER THE INITIAL TEST, THE PROPERTY OWNER IS RESPONSIBLE FOR THE TEST DUE EACH YEAR ON THE SAME MONTH AS THE INITIAL TEST. THIS TEST SHALL BE COMPLETED BY A CERTIFIED TESTER REGISTERED WITH THE DEPARTMENT OF WATER RESOURCES. A COPY OF A PASSING TEST SHALL BE SUBMITTED TO THE COMPLIANCE SPECIALIST.
6. THE RPDA INSTALLATION IS PRIVATELY OWNED AND MAINTAINED. ALL PIPING ON PRIVATE PROPERTY, EXCLUDING THE RPZ, SHALL BE INSPECTED BY THE CITY BUILDING OFFICIAL.
7. RPDA'S SHALL BE LOCATED AS CLOSE TO THE PROPERTY LINE AND CONNECTION TO THE CITY MAIN AS POSSIBLE UNLESS A WAIVER IS SUBMITTED AND APPROVED IN ADVANCE BY THE DEPARTMENT OF WATER RESOURCES. IF A WAIVER IS GRANTED AND A RPDA IS INSTALLED INSIDE A BUILDING, VERTICAL INSTALLATIONS ARE NOT ALLOWED. CALL 434-455-4216 TO OBTAIN INFORMATION ON THE REQUIRED DOCUMENTATION FOR THE WAIVER REQUEST.
8. A MINIMUM OF 2 FEET SHALL BE ALLOWED AT THE FRONT AND REAR OF EACH ASSEMBLY, WITH A MINIMUM OF 1 FOOT AT EACH END TO ALLOW SUFFICIENT SPACE FOR EASE IN TESTING AND MAINTENANCE.
9. CALCULATIONS TO REVIEW THE AMOUNT OF AVAILABLE WATER PRESSURE AT THE SITE PRIOR TO THE INSTALLATION OF ANY RPZ OR RPDA ASSEMBLY AND THE ESTIMATED EFFECT OF SAID INSTALLATION ARE STRONGLY RECOMMENDED.
10. NO BACKFLOW PREVENTION ASSEMBLY SHALL BE REMOVED, RELOCATED, OR REPLACED WITHOUT PRIOR AUTHORIZATION FROM THE DEPARTMENT OF WATER RESOURCES.
11. ANY FIRE DEPARTMENT CONNECTION (FDC) SHALL BE LOCATED AS PER THE FIRE MARSHAL AND NFPA. ALL FDC'S MUST BE DOWNSTREAM OF THE RPZ OR RPDA.



THE CITY OF LYNCHBURG

RPDA-FOR INDEPENDENT FIRE SERVICE
OR PRIVATE HYDRANT INSTALLATION

USE WITH THE CITY OF LYNCHBURG STANDARD SPECIFICATIONS ONLY

SCALE:
NOT TO SCALE

REVISION DATE:
12-15-2016

DETAIL #
26.20A

SHEET #:
2 OF 3