

- 1. MEG-A-LUGS MAY BE SUBSTITUTED FOR TIE RODS UPON APPROVAL BY THE CITY ENGINEER.
- 2. CHAINS ON FIRE HYDRANTS TO BE REMOVED.
- 3. HYDRANTS TO BE PLACED WITH PUMPER NOZZLE FACING THE STREET OR AS OTHERWISE DIRECTED.
- 4. WHEN VALVE BOX IS PLACED OUTSIDE OF PAVEMENT, PROVIDE PRECAST SHOULDER SLAB. (DETAIL 26.18)
- 5. WHEN FIRE HYDRANTS ARE INSTALLED WHERE ROADWAY HAS A DRAINAGE DITCH AND NO CURB & GUTTER, MINUMUM COVER SHALL BE 24" FROM THE BOTTOM OF DITCH.
- 6. SEE TIE ROD CHART (DETAIL 26.03) FOR NUMBER OF RODS REQUIRED.
- 7. WHERE HYDRANT IS SET BEHIND GUARDRAIL, CENTERLINE OF PUMPER NOZZLE TO BE A MINIMUM OF 12" AND A MAXIMUM OF 18" ABOVE TOP OF GUARDRAIL.



YNCHBURG

TYPICAL

USE WITH THE CITY OF LYNCHBURG STANDARD SPECIFICATIONS ONLY

SCALE: NOT TO SCALE

DETAIL # 26.09

REVISION DATE:

SHEET #: OF **1**

10-21-04